

1993

COMMISSION

CALHOUN COUNTY  
REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

CLERK-REGISTER  
CALHOUN COUNTY, MICH.  
ANNIE B. NORLANDER

SEP 1 10 32 AM '93

RECORDED

Register of Deeds Stamp & File Number

For corners in  
CALHOUN

(County)

Located In:

Corner Code #

1. Public Land Survey	T 3 S R 8W	H-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

DONALD J. DAVIS, in a field survey on JULY 22, 1993,  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

1. Description of original monument and accessories and/or subsequent restoration:

TILE SET IN RESURVEY OF 1885, BY F. HODGEMAN IN 1885.  
14" BEECH N 26° E 25 LINKS.  
14" BEECH N 80° W 28 LINKS.

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND TILE IN SWAMP.  
NO ORIGINAL WITNESSES EXIST.

3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET BERNSTEIN STAINLESS STEEL MONUMENT WITH BRONZE CAP WITH ROCKS AROUND OVER BOTTOM SECTION  
OF TILE.  
12" ELM N 45° W 26.21' NAIL & SPOTTER.  
12" RED OAK N 20° E 34.62' NAIL & SPOTTER.  
8" YELLOW BIRCH EAST 9.38' NAIL & SPOTTER.  
12" HICKORY S 80° E 9.87' NAIL & SPOTTER.  
NO OCCUPATION NEAR CORNER.



Signed by Donald J. Davis  
Surveyor's Michigan License No. 17617

Date August 1, 1993