

1993

COMMISSION

CALHOUN COUNTY
REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

CLERK-REGISTER
CALHOUN COUNTY, MI.
ANNE B. MOORE UNDER

SEP 1 10 32 AM '93

RECORDED

For corners in
CALHOUN

(County)	Located In:	Corner Code #
Public Land Survey	T 3 S R 8 W	I-6
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
1. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

1. Lot No. _____, Recorded Plat _____
2. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

DONALD J. DAVIS, in a field survey on JULY 23, 1993.

I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1. Description of original monument and accessories and/or subsequent restoration:

TILE SET IN 1885 RESURVEY.
NO WITNESSES REMAIN OTHER THAN "CROSSOVER".
8" BUTTERNUT S 39° E 6½ LINKS.
20" ASH N 12° W 9 LINKS.

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CROSSOVER AND TILE IN SURVEY IN 1986 4.5 FEET UNDER ROAD, SET 5/8" IRON.
6' EAST OF CENTERLINE OF ROAD.
CENTERLINE IRON CORNER EAST 23.10'.
30" ASH N 25° W 84.70'.
35" OAK S 30° E 70.25'.

THIS CORNER ACCEPTED AS A FAITHFUL PERPETUATION OF THE ORIGINAL CORNER.

3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET BERNTSEN STAINLESS STEEL MONUMENT WITH BRONZE CAP IN MONUMENT BOX.
ANGLE IRON POST EAST 23.10'.
30" ASH N 25° W 84.70' NAIL & SPOTTER.
35" OAK S 30° E 70.25' NAIL & SPOTTER.
SE CORNER OF R.R. RAIL POST WEST 36.80'.
6' WEST OF CENTERLINE ROAD.



Signed by Donald J. Davis
Surveyor's Michigan License No. 17617

Date August 12, 1993