

SURVEY & ***
REMONUMENTATION

1993

COMMISSION

CALHOUN COUNTY
REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

CLERK-REGISTERED
CALHOUN COUNTY, MICH.
ANN ARBOR, MICH.
SEP 1 10 32 AM '93

RECORDED

For corners in
CALHOUN

(County)

Located In:

Corner Code #

1. Public Land Survey	T 3 S R 8 W	I-7
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

DONALD J. DAVIS, in a field survey on JULY 22, 1993

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

1. Description of original monument and accessories and/or subsequent restoration:

TILE SET IN RESURVEY OF 1885, BY HODGEMAN.
12" YELLOW OAK S 13° E 35 LINKS.
15" WHITE OAK N 42° E 6 LINKS.

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND TILE WITH 1" PIPE ON TOP. RECORDED IN L.C.R.C. BY GREER IN 1988, LIBER 1471, PAGE 714.
THIS CORNER IS ACCEPTED AS THE TRUE CORNER.

2. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET BERNISEN STAINLESS STEEL MONUMENT WITH BRONZE CAP IN MONUMENT BOX.
TWIN 10" CHERRY S 70° W 40.67' NAIL & SPOTTER.
TWIN 14" HICKORY S 30° W 96.90' NAIL & SPOTTER.
14" CHERRY S 25° E 95.00' NAIL & SPOTTER.
14" CHERRY N 75° E 178.85' NAIL & SPOTTER.
CENTERLINE OF ROADS.



Signed by Donald J. Davis
Surveyor's Michigan License No. 17617

Date August 12, 1993