

APPROVED

Date 12-9-98 *KRC*

CALHOUN COUNTY  
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

15 DEC 1998 3:32:28 PM

ANNE B. NORLANDER  
CLERK - REGISTER OF DEEDS

LIBER **2087** PAGE **916**

Register of Deeds Stamp & File Number

For corners in

Calhoun (County)	Located In:	Corner Code #
Leroy Township		
1. Public Land Survey	T <u>3</u> S R <u>8</u> W	<u>1-9</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William K. Crane, in a field survey on December 3 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO Robert Clark, 1826:

8" Elm N 61° W 44 links  
18" B. Oak S 25° W 30½ links

Resurvey, Hodgman, 1885:

Found stone and brick set by Lewis. Set post with brick under.

10" W. Oak S 69° W 147½ links  
10" Maple S 48° E 73 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found RR spike in pipe over tile and rocks.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced all of above with standard Calhoun County Remonumentation monument (Berntsen monument with monument box) and is accepted as the best available evidence of the location of the original corner.

Nail and tag in guy pole	N 62° E	37.89'
Nail and tag in utility pole	S 47° E	41.50'
Nail and tag in guy pole	N 40° W	44.13'
NE corner of house (corner of siding)	S 20° W	60.27'
SE corner of pole building	N 25° W	83.00'

Signed by William K. Crane

William K. Crane, P.S.

Date December 9, 1998

Surveyor's Michigan License No. 29243

SURVEY &  
REMONUMENTATION

MAR 30 1999

SECTION

