

1993

CALHOUN COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

CALHOUN
(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>3S</u> R <u>8W</u>	<u>I-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECORDED
 OCT 26 10 15 AM 93
 CLERK-REGISTER
 CALHOUN COUNTY, MICH.
 ANNIE R. NOBEL ANDER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, DONALD J. DAVIS, in a field survey on SEPTEMBER 28, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- TILE SET IN RESURVEY OF 1884 BY HODGMAN.
- 16" LYNN S 45° W 28½ LINKS.
- TILE AND ½" COPPER ROD, MDSH 1975.
- 9" SASSAFRASS S 18° E 40.44'.
- 14" SASSAFRASS S 72° W 33.23'.
- CORNER FENCE POST N 88° W 32.75'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- FOUND ½" COPPER ROD IN MONUMENT BOX IN 1" PIPE.
- CHECKED WITH OLD WITNESSES.
- ACCEPTED THIS AS PERPETUATION OF ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET BERNTSEN MONUMENT WITH BRASS CAP IN MONUMENT BOX OVER 1" PIPE.
- NAIL & TAG 14" BASSWOOD N 82° W 39.07'.
- NAIL & TAG TWIN 16" CHERRY N 70° E 46.23'.
- NAIL & TAG 8" MAPLE N 50° E 36.35'.
- WEST FACE 4" STEEL POST EAST 13.13'.
- MDSH TAG WEST 10.23'.
- BOX ON EAST EDGE BUTUMINOUS.

LIBER 1711 PAGE 086



Signed by Donald J. Davis
 Surveyor's Michigan License No. 17617

Date OCTOBER 13, 1993