

MAR 30 1999

APPROVED

Date 9-16-98 RRC  
CALHOUN COUNTY  
REMONUMENTATION

CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

For corners in

CALHOUN  
(County)

Located In:

Corner Code #

LEROY TOWNSHIP  
1. Public Land Survey

T 3S R 8W

K-10

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling  
in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

25 SEP 1998 2:28:43 PM

ANNE B. NORLANDER  
CLERK - REGISTER OF DEEDS

LIBER **2062** PAGE **588**

Register of Deeds Stamp & File Number

I, ROBERT R. CARR, in a field survey on SEPTEMBER 3, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1/4 POST COMMON TO SECTIONS 25 AND 26

A. Description of original monument and accessories and/or subsequent restoration:

ROBERT CLARK, JR, D.S. 1826, SET ORIGINAL CORNER  
F. HODGEMAN, 1889, RESURVEY, FOUND STAKE, STONE AND BRICK IN ROAD  
50 LINKS FROM HEDGE WEST AND IN LINE WITH FENCES EAST AND WEST.  
SURVEY BY D. DAVIS, P.S. 17617 CALLS FOR TILE WITH WITNESSES  
R. CARR, P.S. 20704, 1997 FOUND IRON IN MONUMENT BOX MATCHING DAVIS WITNESSES.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON IN MONUMENT BOX, REMOVED AND FOUND TILE BELOW IRON 2 FEET,  
MORE OR LESS, BELOW ROAD SURFACE.  
REPLACED WITH BERNTSEN REMONUMENTATION MONUMENT AND RESET MONUMENT BOX.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN REMONUMENTATION MONUMENT STAMPED 20704 IN MONUMENT BOX.  
UTILITY POLE, S88°E 26.50 FEET, SET SPOTTER  
40" MAPLE, S25°E 73.59 FEET, SET SPOTTER  
UTILITY POLE, S45°W 44.44 FEET, SET SPOTTER  
14" MAPLE, S68°E 52.93 FEET, SET SPOTTER  
CENTERLINE OF ROAD IS WEST 3 FEET, MORE OR LESS  
IN LINE WITH FENCE EAST.

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.



Signed by [Signature]  
Surveyor's Michigan License No. ROBERT R. CARR 20704

Date SEPTEMBER 16, 1998