

MAR 30 1999

APPROVED

Date 9-16-98 *RCC*
CALHOUN COUNTY
REMONUMENTATION

CALHOUN COUNTY REMONUMENTATION SECTION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

For corners in

25 SEP 1998 2:28:55 PM

ANNE R. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER 2062 PAGE 589

Register of Deeds Stamp & File Number

<u>CALHOUN</u> (County)	Located In:	Corner Code #
LERoy TOWNSHIP	T <u>3S</u> R <u>8W</u>	<u>M-11</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, ROBERT R. CARR, in a field survey on SEPTEMBER 3, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

SOUTHEAST CORNER OF SECTION 25

A. Description of original monument and accessories and/or subsequent restoration:

ROBERT CLARK JR., D.S. 1826, SET ORIGINAL CORNER
F. HODGEMAN, 1889, RESURVEY, SET POST (TILE) FROM STUMP
OF U.S. BEARING TREE.
SURVEY BY DAVIS P.S. NO. 17617, 1975, FOUND TILE 3.96 FEET
SOUTH OF NEWTON CORNER, PLACED ROCKS AROUND.
SURVEY BY CARR P.S. NO. 20704, 1997, FOUND TILE 3.96 FEET
SOUTH OF NEWTON CORNER


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND TILE AND REPLACED WITH BERNTSEN REMONUMENTATION MONUMENT
WITH CARSONITE WITNESS POST BESIDE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN REMONUMENTATION MONUMENT STAMPED 20704
14" ASH, N35°W 17.16 FEET, SET SPOTTER
8" ASH, S40°W 38.71 FEET, SET SPOTTER
8" ASH, N75°E 24.89 FEET, SET SPOTTER
6"&8" TWIN ASH, S39°E 33.05 FEET, SET SPOTTER
TILE AT NEWTON TOWNSHIP CORNER COMMON TO SECTIONS 30 AND 31 NORTH 3.96 FEET.

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.



Signed by *Robert R. Carr*
Surveyor's Michigan License No. ROBERT R. CARR 20704

Date SEPTEMBER 16, 1998