

APR 26 1995

APPROVED

Date 11-28-94  
CALHOUN COUNTY  
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION  
STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

5 DEC 94 10:25 A.M.

ANNE B. NORLANDER  
CLERK - REGISTER OF DEEDS

For corners in  
Calhoun

Located in: Corner Code #

(County)

Homer Twp.

1. Public Land Survey

T 4 S R 4 W

A-5

T R

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

I, Donald J. Davis, in a field survey on November 25, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey in 1826 by Clark. Surveyor A. Chase found axle in 1909 and set tile over. 6" Hickory N 30° E 69', 3" Apple N 40° W 99.5'.

Tile and iron found in 1981 by Fred Cutcher.

18" Hickory N 60° E 56.98'

18" Hickory N 75° E 75.97'

Utility pole S 55° W 45.67'

Utility pole S 70° E 79.15'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found tile over buggy axle in lawn area. Checked with witnesses by Cutcher.

Accepted as good preservation of original corner location.

LIBER 1779 PAGE 373

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Harrison monument 4" under ground level.

Nail & Tag 14" Hickory N 48° E 45.25'

Nail & Tag 6" Burr Oak N 5° W 34.75'

Nail & Tag Utility pole S 70° E 79.15'

Nail & Tag Utility pole S 50° W 57.20'



Signed by

Donald J. Davis

Date November 28, 1994

Surveyor's Michigan License No. 17617