

APR 26 1995

APPROVED
Date 11-28-94
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in
Calhoun

Located In: Corner Code #

Homer Twp.

1. Public Land Survey

T 4 S R 4 W

B-5

T R

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous

S T R

Property in Sec.

S T R

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

5 DEC 94 10:26 A.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5	●												
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Donald J. Davis, in a field survey on November 25, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey in 1826 by Clark.

8" White Oak S 23° W 40½ links.

8" White Oak N 80° E 3 links.

No record of use.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" iron in line with fence south.

Original corner and witnesses destroyed by road construction.

Found SE and SW corners, measured and set post at proportional distance on line.

LIBER 1779 PAGE 372

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Harrison monument in gravel road at proportional measurement.

Nail & Tag 14" White Oak S 55° E 61.05'

Nail & Tag 5" Elm S 15° E 30.50'

Nail & Tag 6" White Oak S 80° W 110.50'

Centerline of gravel road east and west.



Signed by

Donald J. Davis

Date November 28, 1994

Surveyor's Michigan License No. 17617