

1993

CALHOUN COUNTY

CALHOUN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

Nov 19 2 22 PM '93

CLERK-REGISTER
CALHOUN COUNTY, MICH.
ANNE B. NORLANDER

For corners in
Calhoun

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>4S.</u> R <u>4W.</u>	<u>D-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Frederick J.
Cutcher

November 8, 1993

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

North 1/4 post of Sec. 5, T4S, R4W, Homer Twp.

Old records of Calhoun County Road Commission: 54 1/2 links east of T-rail S 1/4 Post of Albion corner (no date or surveyor given).

LCR Liber 1032, Page 608 recorded by DeKeyser Jan. 8, 1974: Set iron by proportional methods.

35.97' East of South 1/4 post Sec. 32, Albion; 3.5' South of East and West road; in line with fence South.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" x 18" iron rod per Part A above.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced 1/2" x 18" iron rod with Bernsten Stainless Steel Marker with brass cap in monument box.

3.5' South of centerline of L Drive S.
35.97' East of South 1/4 post Sec. 32, Albion Twp.
In line with fence South.
N.E. corner of R.R. tie gate post N 42° W 46.40'.

LIBER 1716 PAGE 447

This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

Signed by Frederick J. Cutcher
Surveyor's Michigan License No. 24592

Date November 15, 1993

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

