

1993

COMMISSION

CALHOUN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

CLERK-REGISTER  
 CALHOUN COUNTY  
 ANN ARBOR, MICHIGAN  
 SEP 1 10 30 AM '93

RECORDED

Register of Deeds Stamp & File Number

For corners in Calhoun (County) Located In: \_\_\_\_\_ Corner Code: I-3

1. Public Land Survey	T <u>4S.</u> R <u>4W.</u>	<u>I-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3								9				
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

Frederick J. Cutcher in a field survey on August 4, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Corner common to Sec. 2,3,10 & 11, Town 4 South, Range 4 West, Homer Twp.  
Misc. Calhoun County Surveyor Records (no date or surveyor given): an iron rod and brick; Hickory 8" S. 16° W. 43.2 links.

Spike set by Davis Land Surveying on a survey of property in 1982. This corner was set by measuring lines of occupation North-South-East and West. No witnesses given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found spike as established by Davis Land Surveying, in centerline intersection of gravel roads, and accepted this corner as the best available evidence of the position of the original corner.

No trace of iron rod and brick or 8" Hickory per "A" above, was found by Davis or myself.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced spike set by Davis Land Surveying with a 30" long cast iron Harrison Marker. (Top of Harrison Marker is 6" below gravel road surface).  
In centerline intersection of 28 Mile Rd. & N Drive S.; S.W. cor. house foundation N. 50° E. 122.20'; N.E. cor. garage (siding) S. 10° W. 120.00'; N.E. cor. concrete slab S. 52° W. 103.5'; P.K. nail in W. side of power pole S. 38° E. 157.30'; center of 20" Butternut N. 68° E. 75.20'.



LIBER 1700 PAGE 142

Signed by Frederick J. Cutcher  
Surveyor's Michigan License No. 24592

August 23, 1993