

1993

COMMISSION

CALHOUN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 19

error in first line
T4S R4W is really
T4S R4W Homer
township -
10-25-90
M. Wynn

For corners in
Calhoun (County)

Located In: 4W Corner Code: I-5

Public Land Survey T 4S R 5W

Property Controlling in Section S T R

Miscellaneous Property in Sec. S T R

1. Lot No. Recorded Plat

2. Private Claims

Seq. # 1
SURVEY & REMONUMENTATION
MAY 05 1997

Register of Deeds Stamp & File Number

Frederick J. Cutcher

in a field survey on August 4, 1993

I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner common to Sec. 10, 11, 14 & 15, Town 4 South, Range 4 West, Homer Twp.

1897 County Surveyor Records: Stone 5 x 6 x 12 with x and brick; B. Walnut N 71° 45' W 114'; B. Walnut 7" S 22° 40' E 72.

Records of Davis Land Surveying indicate that stone and brick and references were not found. A P.K. nail was set by measuring lines of occupation North-South-East & West on a survey in 1982.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I dug for this corner on August 4, 1993. No trace of stone or brick was found. I accepted P.K. nail set by Davis Land Surveying as the best available evidence of the position of the original corner.

Walnut trees per above part "A" are gone.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced P.K. nail with aluminum marker with brass cap in monument box. In centerline of P Drive S.; in line with fence to North; top center of telephone stanchion S. 68° W. 58.00'; top center of telephone stanchion N. 65° W. 51.20'; nail in 14" Ash N. 13° W. 36.60'; nail in 20" Hickory S. 60° E. 61.70'; top center of telephone stanchion N. 52° W. 32.90'.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Signed by Frederick J. Cutcher
Surveyor's Michigan License No. 24592



August 23, 1993

LIBER 1700 PAGE 146