

APPROVED

Date 11-12-96  
CALHOUN COUNTY  
REMONUMENTATION.  
For corners in  
Calhoun

CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

19 FEB 97 3:48 P.M.

ANNE B. NOSLANDER  
CLERK - REGISTER OF DEEDS

LIBER 1916 PAGE 107

Register of Deeds Stamp & File Number

	Located In:	Corner Code #
HOMER TWP.		
1. Public Land Survey	T <u>4S</u> R <u>4W</u>	<u>K-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

HOMER TWP.

I, Donald J. Davis, in a field survey on October 24, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey in 1826 by Clark.  
1" pipe found and used by Crane in 1993.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" pipe that matched witnesses by Crane.  
Accepted as good location for corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Harrison monument at location, 5' west of centerline of gravel road.  
Nail & Tag 46" Oak N 75° W 33.92'  
Nail & Tag 18" Hickory N 80° E 34.44'  
Nail & Tag 36" Oak N 30° W 83.31'  
Nail & Tag 18" Hickory N 35° E 84.91'  
In line with fence west.

SURVEY &  
REMONUMENTATION

APR 07 1998

SECTION



Signed by Donald J. Davis  
Surveyor's Michigan License No. 17617

Date 2/3/97