

APPROVED

Date 11-12-96

CALHOUN COUNTY REMONUMENTATION

CALHOUN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN CALHOUN COUNTY RECORDED

19 NOV 96 1:59 P.M.

ANNE B. NORLANDER CLERK - REGISTER OF DEEDS

LIBER 1899 PAGE 613

Register of Deeds Stamp & File Number

Form with fields for Calhoun (County), Located In, Corner Code #, and numbered items 1-5 for survey details.

Grid table with columns A-M and rows 2-13, containing numbers 1-36.

I, Donald J. Davis, in a field survey on October 24, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: Original survey by Clark in 1826. Corner set on line. 3/4" rebar found and used in survey by Crane in 1993. Hillsdale County corner was found 7.48 feet west.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Found 3/4" rebar at corner location and matched witnesses by Crane. Utility Pole N 70° W 69.49' 24" Oak East 80.08 feet

SURVEY & REMONUMENTATION MAR 21 1997 COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: Set Harrison monument in gravel road. Nail & Tag utility pole N 70° W 69.70' Nail & Tag 24" Oak N 80° E 80.05' Nail & Tag 24" Oak N 25° W 151.34' Nail & Tag Twin 12" Elm N 55° E 44.35'



Signed by Donald J. Davis, Surveyor's Michigan License No. 17617

Date October 31, 1996