

APPROVED

Date 9-15-99 RRC

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

For corners in

CALHOUN
(County)

Located in:

Corner Code #

29 SEP 1999 10:32:21 AM

HOMER TWP

1. Public Land Survey

T 4S R 4W

M-2

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER 2164 PAGE 719

2. Property Controlling
In Section

S T R
S T R

3. Miscellaneous
Property in Sec.

S T R
S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	19		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Michael A. Groat, in a field survey on August 17, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL SURVEY BY ROBERT CLARK, 1825, SET POST, W. OAK, 30", N 63° W, 17 LINKS, W. OAK, 22", S 39 1/2° W 29 LINKS.
DON DAVIS, P.S., NO DATE, 3/4" PIPE, 10" OAK, N 75° W, 98.80' 24" OAK, N 25° W, 117.27', 8" HICKORY, N 40° E, 47.50'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


FOUND 3/4" PIPE IN MONUMENT BOX EXCAVATED & FOUND PARTS OF CLAY TILE. FOUND 2" PIPE BENEATH TILE. ACCEPTED THE POSITION OF THE 3/4" PIPE AS THE BEST EVIDENCE OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET BERNTSEN MONUMENT IN MONUMENT BOX.
2" STEEL POST IN CONCRETE, S 36° W, 49.20 FEET
SW CORNER OF HOUSE FOUNDATION # 6475, N 85° E, 124.95'
FOUND NAIL IN 25" WALNUT, N 58° W, 24.89 FEET
SET NAIL IN WHITE OAK, N 20° E, 117.00 FEET

Signed by [Signature]
Surveyor's Michigan License No. 39079

Date September 13, 1999



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 26, 1971
REVISED MAY 14, 1975
REVISED JAN, 1983
REVISED OCT., 1986

SURVEY &
REMONUMENTATION

MAR 13 2000

SECTION