

APPROVED

Date 9-15-99 RRC

CALHOUN COUNTY  
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

For corners in

CALHOUN  
(County)

Located in:

Corner Code #:

HOMER

1. Public Land Survey

T 4S R 4W

M-3

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

2. Property Controlling  
in Section

S \_\_\_

T \_\_\_ R \_\_\_

S \_\_\_

T \_\_\_ R \_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_

T \_\_\_ R \_\_\_

S \_\_\_

T \_\_\_ R \_\_\_

29 SEP 1999 10:32:09 AM

ANNE H. NORLANDER  
CLERK - REGISTER OF DEEDS

LIBER 2164 PAGE 718

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Michael A. Groat, in a field survey on September 13, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL SURVEY, ROBERT CLARK, DEPUTY SURVEYOR, 1826, SET POST, W. OAK, 32° S 33 1/2° W, 22 LINKS; W. OAK, N 13 1/2° W, 79 LINKS.  
T.P.J., NO DATE, 3/4" PIPE, 5" EAST OF CENTERLINE, 68.5' NORTH OF FENCE EAST, 10" R. OAK, N 75° W, 98.60';  
24" W. OAK, N 25° W, 117.27'; 8" HICKORY, N 40° E, 47.50'.  
DONALD J. DAVIS, P.S., NO DATE, HAD THE SAME AS T.P.J.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND LARGE NAIL IN 3/4" X 6" PIPE, 2' DOWN FOUND STONE, (8" X 8") ACCEPTED THE POSITION OF THE STONE AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET BERNTSEN MONUMENT IN MONUMENT BOX IN PLACE OF THE 3/4" PIPE.  
FOUND NAIL IN 18" HICKORY, N 40° E, 47.50 FEET  
FOUND NAIL & TAG IN 25" RED OAK, N 65° W, 98.61 FEET  
SET NAIL & TAG IN 36" RED OAK, N 15° W, 116.95 FEET  
SET NAIL & TAG IN 15" CHERRY, S 46° E, 29.64 FEET

Signed by [Signature]  
Surveyor's Michigan License No. 39079

Date September 15, 1999



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1979  
REVISED JAN., 1983  
REVISED OCT., 1988

SURVEY &  
REMONUMENTATION

MAR 13 2000

SECTION