

APPROVED

Date 12/8/99 MLC
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

For corners in

<u>CALHOUN</u> (County)	Located In:	Corner Code #
HOMER TOWNSHIP		
1. Public Land Survey	T <u>4S</u> R <u>4W</u>	<u>M-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

17 DEC 1999 2:34:38 PM

AGNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER 2185 PAGE 994

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	⊕
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Michael A Groat, in a field survey on December 2, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL SURVEY BY ROBERT CLARK, 1826, SET POST, W. OAK 17", S 27° W, 63 LINKS, W. OAK, 18", N 37° W, 105 LINKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO PHYSICAL EVIDENCE AT SURFACE OF ROAD. A PRO-RATED ON LINE DISTANCE BETWEEN M-3 & M-5 LINES UP VERY WELL WITH OCCUPATION RUNNING WEST. GOVERNMENT DISTANCE WOULD PUT THE JACKSON CORNER 68.97 FEET SOUTH AND WE FOUND A 1" PIPE 69.08' SOUTH, ON LINE. EXCAVATED BUT FOUND NO EVIDENCE OF THE ORIGINAL CORNER. ACCEPTED THE PRO-RATED ON LINE DISTANCE BETWEEN M-3 & M-5 AS THE BEST EVIDENCE OF THE LOCATION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET BERNTSEN MONUMENT & MONUMENT BOX
NAIL & TAG IN 8" OAK, S 40° W, 51.85'
NAIL & TAG IN 15" OAK, N 45° W, 42.71'
FENCE POST, N 60° E, 33.81'
NW CORNER OF BARN, S 70° E, 58.55'
4.5' EAST OF CENTERLINE



Signed by [Signature]
Surveyor's Michigan License No. 39079

Date December 7, 1999

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1976
REVISED JAN., 1983
REVISED OCT., 1986

SURVEY &
REMONUMENTATION

MAR 13 2000

SECTION