

**APPROVED**

Date 5-19-99 RRC  
**CALHOUN COUNTY**  
REMONUMENTATION

**CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

14 JUN 1999 1:59:27 PM

ANNE B. NORLANDER  
CLERK - REGISTER OF DEEDS

LIBER **2134** PAGE **503**

Register of Deeds Stamp & File Number

For corners in

<u>CALHOUN</u>	Located In:	Corner Code #
(County)		
HOMER TOWNSHIP		
1. Public Land Survey	T <u>4S</u> R <u>4W</u>	<u>M-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Michael A. Groat, in a field survey on March 30, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		6		9		10		11		12	
5													
6		16		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A Description of original monument and accessories and/or subsequent restoration:


ORIGINAL SURVEY, R. CLARK, DEPUTY SURVEYOR, 1826, SET POST, W. OAK, 18", N 2° W, 11.66 LKS, NO OTHER TREES NEAR.  
J. ALDEN, 1964, R.R. SPIKE, 12" OAK, S 15° W, 90.8', 22" OAK, N 15° W, 86.7', 18" OAK, WEST, 49.65'.  
1977, "TPJ", R.R. SPIKE, 12" OAK, S 15° W, 90.8', 22" OAK, N 15° W, 86.7', 18" OAK, WEST, 49.65'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND R.R. SPIKE AS CALLED FOR ABOVE, CHECKED INTO REMAINING WITNESSES, EXCAVATED, FOUND NOTHING ELSE. ACCEPTED THE POSITION OF THE R.R. SPIKE AS THE BEST EVIDENCE OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET A BERNTSEN MONUMENT IN MONUMENT BOX. STAMPED CORNER CODE INFORMATION IN BRASS CAP.  
NAIL & TAG IN 16" OAK, S 20° W, 90.55'  
NAIL & TAG IN 30" OAK, N 10° W, 86.83'  
NAIL & TAG IN 24" OAK, WEST, 49.65'  
NAIL & TAG IN 4" OAK, S 60° W, 39.95'



Signed by [Signature]  
Surveyor's Michigan License No. 39079

Date March 30, 1999

**SURVEY &  
REMONUMENTATION**

MAR 13 2000

SECTION