

**APPROVED**

Date 5-19-99 *RLL*  
**CALHOUN COUNTY  
REMONUMENTATION.**

**CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

14 JUN 1999 1:58:57 PM

ANNE B. NORLANDER  
CLERK - REGISTER OF DEEDS

LIBER **2134** PAGE **501**

Register of Deeds Stamp & File Number

For corners in

|                                       |   |               |
|---------------------------------------|---|---------------|
| <u>CALHOUN</u><br>(County)            | Located In:                               | Corner Code # |
| HOMER TOWNSHIP                        |   |               |
| 1. Public Land Survey                 | T <u>4S</u> R <u>4W</u>                   | <u>M-7</u>    |
|                                       | T <u>    </u> R <u>    </u>               | <u>    </u>   |
|                                       | T <u>    </u> R <u>    </u>               | <u>    </u>   |
|                                       | T <u>    </u> R <u>    </u>               | <u>    </u>   |
| 2. Property Controlling<br>in Section | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u>   |
|                                       | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u>   |
| 3. Miscellaneous<br>Property in Sec.  | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u>   |
|                                       | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u>   |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Michael A. Groat, in a field survey on March 30, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    |   |    |   |    |   |    |   |    |   |    |   |    |   |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1  | A | B  | C | D  | E | F  | G | H  | I | J  | K | L  | M |
| 2  |   | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |
| 3  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 4  |   | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |
| 5  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 6  |   | 16 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |
| 7  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 8  |   | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |
| 9  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 10 |   | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |
| 11 |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 12 |   | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |
| 13 |   |    |   |    |   |    |   |    |   |    |   |    |   |

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL SURVEY, 1826, ROBERT CLARK, SET POST, W. OAK, 12", N 46° W, 88 LKS,  
W. OAK, S 47-1/2° W, 43 LKS.  
WITNESS CARD "ARNTS", 1927, 14" W. CHERRY, S 20° E, 96.4', 36" OAK, N 45° W, 58.7', 3" CHERRY, N 30° E, 58.3'  
J. ALDEN, 1964, IRON, 36" OAK, N 50° W, 59.4', SE CORNER HOUSE FND., NW, 97.6", 25" OAK, N 30° W, 70.05', 32" OAK,  
S 20° W, 86.1'.  
"TPJ", 1977, SAME AS ALDEN ABOVE.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND IRON MATCHING WITNESSES FROM ABOVE. EXCAVATED, FOUND PIECES OF BRICK AND LARGE STONE.  
ACCEPTED THE POSITION OF THE IRON AS THE BEST EVIDENCE OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET BERNTSEN MONUMENT IN MONUMENT BOX IN PLACE OF IRON. STAMPED CORNER INFORMATION  
IN BRASS CAP.  
SW CORNER OF HOUSE FOUNDATION, N 34° W, 97.41'  
NAIL & TAG IN 24" OAK, N 20° W, 69.50'  
NAIL & TAG IN 40" OAK, N 40° W, 58.90'  
SE CORNER OF CONC. PAD, N 70° W, 139.95'  
1/2" IRON, SOUTH 30.05'



Signed by [Signature]  
Surveyor's Michigan License No. 39079

Date March 30, 1999

**SURVEY &  
REMONUMENTATION**

MAR 13 2000

SECTION