

APPROVED

Date 12/8/99 RRC  
CALHOUN COUNTY  
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

For corners in

<u>CALHOUN</u>	Located In:	Corner Code #
(County)		
HOMER TOWNSHIP		
1. Public Land Survey	T <u>4S</u> R <u>4W</u>	<u>M-8</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

17 DEC 1999 2:33:59 PM

ANNE G. NORLANDER  
CLERK - REGISTER OF DEEDS

LIBER **2185** PAGE **991**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Michael A Groat, in a field survey on December 2, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL SURVEY BY ROBERT CLARK, 1826, SET POST, W. OAK, 8", N 42 1/2 ° W, 52 LINKS, W. OAK, 5", S 72° W, 40 LINKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO PHYSICAL CORNER AT SURFACE OF THE ROAD. THERE IS A FENCE RUNNING WEST FOR CALHOUN COUNTY, AND A FENCE RUNNING EAST FOR JACKSON COUNTY. THE GOVERNMENT JOG AT THIS CORNER WOULD BE 35.31 FEET, HOWEVER THE FENCES ONLY MEASURE 5 FEET A PART. THERE IS A IRON IN A MONUMENT BOX AT THE EXTENSION OF THE EASTERLY FENCE. NO RECORD OF THIS IRON CAN BE FOUND AND IT APPEARS TO HAVE BEEN SET IN THE CENTERLINE OF THE ROAD & EXTENSION OF THE FENCE. A PRO-RATION OF THE LINE FROM M-11 TO M-7 WOULD PUT THIS CORNER (M-8) 6' ± NORTH OF THE WESTERLY FENCE. EXCAVATION WAS DONE AT THE EXTENSION OF THE FENCE AND 6' ± NORTH. NO EVIDENCE OF THE ORIGINAL CORNER COULD BE FOUND. SET A BERNTSEN MONUMENT AT PRO-RATED DISTANCE ON LINE BETWEEN M-7 & M-11. ACCEPTED THIS LOCATION AS THE BEST AVAILABLE EVIDENCE OF THE CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET BERNTSEN MONUMENT & MONUMENT BOX.  
STEEL FENCE CORNER POST, S 74° W, 34.2'  
NAIL & TAG IN 30" OAK, S 10° W, 140.2'  
NAIL & TAG IN 18" POPLAR, S 25° E, 53.6'  
NAIL & TAG IN 10" OAK, S 75° E, 32.24'  
IRON IN BOX, SOUTH, 14.10'  
1' EAST OF CENTERLINE OF ROAD



Signed by [Signature]  
Surveyor's Michigan License No. 39079

Date December 7, 1999

SURVEY &  
REMONUMENTATION

MAR 13 2000

SECTION