

APPROVED

Date 12/13/99
RRC

CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

17 DEC 1999 2:35:07 PM

MINE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER 2185 PAGE 996

Register of Deeds Stamp & File Number

For corners in

<u>CALHOUN</u>	Located In:	Corner Code #
(County)		
HOMER TOWNSHIP		
1. Public Land Survey	T <u>4S</u> R <u>4W</u>	<u>M-9</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael A. Groat, in a field survey on December 2, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL SURVEY 1826, ROBERT CLARK, SET POST, B. OAK, 9" S 53° W 24 LINKS, B. OAK, N 68° W, 32 LINKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO PHYSICAL EVIDENCE AT SURFACE. THE GOVERNMENT JOG AT THIS CORNER IS 24.42 FEET. NO OCCUPATION WEST. THERE IS A PIPE IN A BOX IN THE CENTERLINE OF ROAD RUNNING EAST AND NORTH AND SOUTH. NO RECORD OF THIS CORNER COULD BE FOUND & IT APPEARS TO HAVE BEEN SET AT CL-CL. A PRO-RATION FROM M-7 & M-11 PUTS THIS CORNER (M-9) 5' EAST OF CENTERLINE AND 18.37' NORTH OF THE JACKSON CORNER. EXCAVATION AT THE PRO-RATED LOCATION AND FOUND NOTHING. EARTHWORK APPEARS TO HAVE BEEN DONE AT THIS ROAD INTERSECTION. SET A BERNTSEN MONUMENT AND MONUMENT BOX AT PRO-RATED DISTANCE ON LINE BETWEEN M-7 & M-11. ACCEPTED THIS LOCATION AS THE BEST POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET BERNTSEN MONUMENT & MONUMENT BOX
NAIL & TAG IN 30" OAK, N 20° E, 95.11'
NAIL & TAG IN 16" HICKORY, N 25° W, 92.46'
NAIL & TAG IN 18" MAPLE, S 40° E, 60.2'
NAIL & TAG IN 12" HICKORY, S 50° E, 76.69'
5' EAST OF CENTERLINE
18.37' NORTH OF PIPE.



Signed by [Signature]
Surveyor's Michigan License No. 39079

Date December 7, 1999

SURVEY &
REMONUMENTATION

MAR 13 2000

SECTION