

APPROVED

Date 12/8/99 ACL
CALHOUN COUNTY
REMONUMENTATION

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 CALHOUN COUNTY
 RECORDED

For corners in

N.

17 DEC 1999 2:34:55 PM

CALHOUN
 (County)

Located In:

Corner Code #

HOMER TOWNSHIP
 1. Public Land Survey

T.4S R.4W M-10

T. R.

T. R.

T. R.

2. Property Controlling
 in Section

S. T. R.

S. T. R.

3. Miscellaneous
 Property in Sec.

S. T. R.

S. T. R.

ANNE R. NORLANDER
 CLERK - REGISTER OF DEEDS

LIBER **2185** PAGE **995**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Michael A. Groat, in a field survey on December 2, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL SURVEY BY ROBERT CLARK, 1826, SET POST, W. OAK 16", N 40° W, 38 LINKS; W. OAK, 9", S 71° W, 45 1/2 LINKS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO PHYSICAL EVIDENCE AT SURFACE FOR THIS CORNER. JACKSON COUNTY FENCE LINE RUNNING EAST, 34.7 FEET (GOVERNMENT WOULD BE 34.0'). THIS CORNER FALLS ON THE DOWN SIDE OF A STEEP HILL AND A LOT OF EARTHWORK HAS BEEN DONE. CORNER LOCATION WAS RE-ESTABLISHED ON LINE AT A PRO-RATED DISTANCE FROM M-7 & M-11. ACCEPTED THIS LOCATION AS THE BEST EVIDENCE OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET BERNTSEN MONUMENT IN MONUMENT BOX
 NAIL & TAG IN 6" OAK, N 40° W, 37.15'
 NAIL & TAG IN 32" OAK, S 47° W, 49.7'
 NAIL & TAG IN 16" OAK, S 70° E, 31.5'
 NAIL & TAG IN 12" OAK, S 17° E, 73.25'
 3' WEST OF CENTERLINE OF ROAD



Signed by Michael A. Groat
 Surveyor's Michigan License No. 39079

Date December 7, 1999

SURVEY &
 REMONUMENTATION

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1976
 REVISED JAN., 1983
 REVISED OCT., 1986

MAR 13 2000

SECTION