

**APPROVED**  
 Date 11-12-96  
**CALHOUN COUNTY**  
**REMONUMENTATION.**

**CALHOUN COUNTY REMONUMENTATION**  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
 CALHOUN COUNTY  
 RECORDED

For corners in  
**Calhoun**

Located In: \_\_\_\_\_ Corner Code #/

19 NOV 96 1:58 P.M.

(County)  
**HOMER TWP.**

1. Public Land Survey	T <u>4S</u> R <u>4W</u>	<u>M-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

ANNE B. NORLANDER  
 CLERK - REGISTER OF DEEDS

LIBER **1899** PAGE **611**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Donald J. Davis, in a field survey on October 25, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

HOMER TWP.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey in 1826 by Clark.  
 No records of use or location of point.

**SURVEY &  
 REMONUMENTATION**

MAR 21 1997

COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found no evidence of corner location except the occupation fence east into Jackson County (43.56 feet south) and location of occupation fences in Section 36 of Calhoun County match section splits good.  
 Used the fences and occupation to set the location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument in monument box.  
 Centerline of North and South road.  
 Nail & Tag 40" Maple S 15° E 172.35'  
 Nail & Tag 20" Maple S 12° W 179.72'  
 Nail & Tag 14" Hickory N 70° W 55.10'  
 Nail & Tag 40" Maple N 22° E 73.48'  
 Fence East 43.56' South.



Signed by Donald J. Davis  
 Surveyor's Michigan License No. 17617

Date October