

APPROVED

Date 11-12-96

CALHOUN COUNTY
REMONUMENTATION.
For corners in
Calhoun

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

19 NOV 96 1:58 P.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER 1899 PAGE 610

Register of Deeds Stamp & File Number

| | Located In: | Corner Code # |
|---------------------------------------|-------------|---------------|
| (County) HOMER TWP. | | |
| 1. Public Land Survey | T 4S R 4W | M-12 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Donald J. Davis, in a field survey on October 25, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Original survey in 1826 by Clark.
No other record of use on location.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

HOMER TWP.

**SURVEY &
REMONUMENTATION**

MAR 21 1997

COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
No witnesses or evidence of corner location.
Reset corner location on line between northeast and southeast corner of section at proportional distance (1/2) as called for in original survey. This matches very good with occupation fences in Section 36 and Section 31 of Scipio Township, Jackson County.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set Berntsen monument in monument box in centerline of bituminous road.
Nail & Tag utility pole S 89° E 228.66'
Nail & Tag 48" Maple N 4° E 308.20'
SE corner house #12393 foundation N 13° E 411.94'
Nail & Tag 10" Maple S 5° E 331.66'



Signed by Donald J. Davis
Surveyor's Michigan License No. 17617

Date October 31, 1996