

APPROVED

date 11-12-96

CALHOUN COUNTY REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN CALHOUN COUNTY RECORDED

19 NOV 96 1:58 P.M.

ANNE B. NORLANDER CLERK - REGISTER OF DEEDS

LIBER 1899 PAGE 612

Register of Deeds Stamp & File Number

Table with columns: (County) Calhoun, Located In: HOMER TWP., Corner Code #: M-13. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

Grid map showing sections 1-36 in Homer Twp. Columns A-M, rows 1-13.

Donald J. Davis, in a field survey on October 25, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey in 1826 by Clark. No records of corner location. 18" Black Oak N 8° E 92 links. 24" Black Oak S 55° W 127 links.

SURVEY & REMONUMENTATION

MAR 21 1997


COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

General location area dug by Jackson County Road Commission, 8 foot by 5 foot hole 5 feet deep dug, no evidence found. Used old boundary markers of old cemetery in Section 31 of Scipio Township, Jackson Co. to establish location east and west and all occupation in Sections 36 and 35 of Homer Township to establish location north and south. Occupation of land in Sections 31 and 30 of Scipio Township, Jackson County matched good for location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument in monument box. SW corner of house foundation N 56° E 100.35' Nail & Tag 40" White Oak N 26° W 57.55' Nail & Tag 40" Willow N 32° E 78.19' Nail & Tag 12" Juniper N 70° E 79.63' Nail & Tag 38" Red Oak S 23° W 54.47' Centerlines of Roads North, South and East.



Signed by Donald J. Davis, Surveyor's Michigan License No. 17617

Date October 31, 1996