

MAY 05 1997

This is recorded to correct Range designation on Liber 1700 page 146

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

25 MAR 97 12:30 P.M.

ANNE B. NORLANDER  
CLERK - REGISTER OF DEEDS

For corners in

CALHOUN

(County)

Located In:

Corner Code ##

Homer Twp.

T 4S R 4W

I-5

1. Public Land Survey

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

*Seg. # 3*

2. Property Controlling in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Fredrick J Cutcher, in a field survey on August 4, 1993, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Corner common to sec 10, 11, 14 and 15 Town 4 South, Range 4 West Homer Township.

1897 County surveyor records; Stone 5 x 6 x 12 with X and Brick; B. Walnut N71 45"W 114', B Walnut 7" S22 40" E 72'

Records of Davis Land surveying indicate that stone and brick and references were not found. a PK Nail was set by measuring lines of occupation north-south-east and west on a survey in 1982.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I dug for this corner on August 4, 1993. No trace of stone or brick was found. I accepted PK nail set by Davis Land Surveying as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced PK Nail with Calhoun County Remonumentation monument in Mon Box.

Falls in centerline of P Drive South in line with fence to north.

top center of telephone station S68 W 58.00' Top center of telephone station N 65 W 51.20 feet; nail in 14" ash N13 W 36.60' ; Nail in 20" Hickory S60E 61.70' ; Top center of telephone station N52 W 32.90 feet.

Signed by Fredrick J. Cutcher  
Surveyor's Michigan License No. Fredrick J Cutcher 24592

Date MARCH, 25, 1997  
~~August 23, 1993~~

LIBER 1922 PAGE 382