

SURVEY & REMONUMENTATION

FEB 02 1999

**CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

9 OCT 96 10:47 A.M.

SECTION

For corners in

Calhoun
(County)

Located In:

Corner Code #

1. Public Land Survey

T 4 S R 4 W

I-5

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
In Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

ANNE D. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER **1890** PAGE **949**

Register of Deeds Stamp & File Number

I, Donald J. Davis, in a field survey on August 4, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5											
3													
4	7	8	9	10	11	12							
5									●				
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Homer Twp.

A. Description of original monument and accessories and/or subsequent restoration:

Corner common to Sec. 10, 11, 14 & 15, Town 4 South, Range 4 West, Homer Twp.
1897 County Surveyor Records: Stone 5 x 6 x 12 with x and brick; B. Walnut N 71° 45' W 114'; B. Walnut S 22° 40' E 72'

Records of Davis Land Surveying indicate that stone and brick references were not found. A P.K. nail was set by measuring lines of occupation North-South-East & West on a survey in 1982.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I dug for this corner on August 4, 1993. No trace of stone or brick was found. I accepted P.K. nail set by Davis Land Surveying as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replace P.K. nail with aluminum marker with brass cap in monument box.
In centerline of P Drive South; in line with fence to North; top center of telephone stanchion S 68° W 58.00'; top center of telephone stanchion N 65° W 51.20'; nail in 14" Ash N 52° W 32.90'.



Signed by Donald J. Davis
Surveyor's Michigan License No. 17617

October 4, 1996