

APPROVED

MAR 30 1999

Date 7-15-98  
CALHOUN COUNTY  
REMONUMENTATION.

Calhoun County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

20 JUL 1998 1:54:06 PM

For corners in

Calhoun _____	Located In:	Corner Code #
(County)		
Clarendon		
1. Public Land Survey	T <u>4S</u> R <u>5W</u>	<u>E-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____	_____
in Section	S _____ T _____	_____
3. Miscellaneous	S _____ T _____	_____
Property in Sec.	S _____ T _____	_____

ANNE B. NORLANDER  
CLERK - REGISTER OF DEEDS  
LIBER **2044** PAGE **157**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Michael A. Groat, in a field survey on July 9, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	H
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	16		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL SURVEY BY ROBERT CLARK, 1826, 77.62 INTERSECTED THE NORTH BOUNDARY 42 LINKS EAST OF POST; W. OAK 13"; S 68 DEGREES W, 55 LINKS; B. OAK, 16", S 35 E, 60 LKS. NO NAME OR DATE: PLOW POINT WITH STONE, Y. OAK STUMP, S 68 DEGREES W, 55 LKS; 4" HICKORY 0.38"; R. OAK, 6"; 78 7/8; CHERRY, 8", .45  
LAWRENCE, 1959, DOES NOT SAY WHAT THE CORNER IS, 7" ELM, N 9 DEGREES E, 21.83"; 18" HICKORY, S 24 DEGREES E, 24.61"; 14" WALNUT, S 20 DEGREES E.  
FRED CUTCHER, P.S., 6-17-81, FOUND IRON 8"+/- BELOW ROAD, BENT, RE-SET WITH RE-BAR & CAP; R.R. TRACK FENCE CORNER, SOUTH 25.3; 29' EAST OF FENCE NORTH; P.P., S 55 DEGREES W, 91.70'  
MICHAEL GROAT, P.S., NOVEMBER 1997, FOUND RE-BAR; 18" OAK, 332 DEGREES NAZ, 31.75'; 14" WALNUT, 50 DEGREES NAZ, 48.31'; 22" HICKORY, 160 DEGREES NAZ, 25.73'; 22" WALNUT, 240 DEGREES NAZ, 59.65.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CAPPED IRON AT ROAD SURFACE, EXCAVATED AND FOUND PIPE, BELOW PIPE FOUND CLAY POTTERY & PLOW POINT & LARGE ROCK. ACCEPTED THE POSITION OF THE CAPPED IRON AS THE BEST EVIDENCE OF THE ORIGINAL CORNER. SET BERNTSEN MONUMENT & MONUMENT BOX.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

THE CORNER IS A BERNTSEN MONUMENT WITH CORNER INFORMATION AND P.S. # STAMPED IN CAP  
CORNER IS 0.49' SOUTH OF TOWNSHIP LINE  
NAIL & TAG IN WESTERLY SIDE OF 24" HICKORY, 123 DEGREES NAZ, 44.47'  
NAIL & TAG IN WESTERLY SIDE OF 20" WALNUT, 217 DEGREES NAZ, 39.89'  
NAIL & TAG IN SOUTHEASTERLY SIDE OF 14" WALNUT, 67 DEGREES NAZ, 71.73'  
NAIL & TAG IN EASTERLY SIDE OF 15" OAK, 28 DEGREES NAZ, 27.99'  
CORNER MEASURES 28.13 FEET EAST OF ECKFORD CORNER

NOTE: NAZ=MAGNETIC AZIMUTH MEASURED FROM NORTH



Signed by Michael A. Groat  
Surveyor's Michigan License No. 39079

Date 7-9-98