

APPROVED

Date 7-27-94
**CALHOUN COUNTY
REMONUMENTATION.**

CLAHOUN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

28 JUL 94 11:14 A.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in
Calhoun
(County)

Located In: _____ Corner Code E-4

1. Public Land Survey T 4 S R 5 W _____
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Donald J. Davis, in a field survey on July 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Clark, 1826

16" White Oak N 6° E 14½ Links

18" White Oak S 18½° W 38½ links

**SURVEY &
REMONUMENTATION**

OCT 24 1994

COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Set midway on line between the Northwest & Southwest corners of Section 9.

Found no evidence of original corner.

LIBER 1760 PAGE 642

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Harrison monument.

Nail & Spotter 12" Ash S 10° W 66.30'

Nail & Spotter 18" Ash N 50° W 35.60'

Nail & Spotter 6" Maple N 60° E 97.20'

Fence corner N 10° W 68.00'



Signed by Donald J. Davis

Date July 25, 1994

Surveyor's Michigan License No. 17617