

APPROVED

Date 11/17/99 *RLC*

CALHOUN COUNTY REMONUMENTATION.

For corners in

CALHOUN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN CALHOUN COUNTY RECORDED

17 DEC 1999 2:44:47 PM

ANNE D. NORLANDER CLERK - REGISTER OF DEEDS

LIBER 2186 PAGE 2

Register of Deeds Stamp & File Number

CALHOUN Located In: Corner Code # (County) CLARENDON TWP.

Table with 3 columns: Survey Description, T/R, E-W. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

4. Lot No. , Recorded Plat

5. Private Claims

I, Frederick J. Cutcher, in a field survey on August 16, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Contains numerical values and a black dot in cell E9.

A. Description of original monument and accessories and/or subsequent restoration:

GLO, 1826, Robert Clark, Jr.: Sugar 14" S. 84 1/2° E. 51 lks; W. Oak 40" S. 44° W. 53 lks.

Witness Card, 1882, Lewis: Same references as GLO.

Witness Card, 11/81, Davis: P.K. centerline of slab; 10" Hickory S. 45° W. 35.60'; 10" Hickory S. 60° E. 65.35'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found P.K. in centerline intersection of T Drive S. and 20 Mile Road.

Two references from Davis' witness card remain.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced P.K. with Bermtsen in monument box and is accepted as the best available evidence of the position of the original corner.

Nail & spotter 18" Hickory S. 40° W. 35.80'; nail & spotter 16" Hickory S. 59° E. 65.30'; N.E. corner tel. stan. bottom S. 34° W. 32.0'; S.E. corner tel. stan. bottom N. 30° W. 37.70'.

SURVEY & REMONUMENTATION

MAR 13 2000

SECTION



Signed by Frederick J. Cutcher Surveyor's Michigan License No. 24592

Date 8/18/99