APPROVED
Date 7-27-94
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

28 JUL 94 11:14 A.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in Calhoun (County)

	Located In:	Corner Code ##
1. Public Land Survey	T 4 S R 5 W	F-5
	T ___ R ___	
	T ___ R ___	
	T ___ R ___	
2. Property Controlling	S ___ T ___ R ___	
in Section	S ___ T ___ R ___	
3. Miscellaneous	S ___ T ___ R ___	
Property in Sec.	S ___ T ___ R ___	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____



I, Donald J. Davis, in a field survey on July 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Clark, 1826
8" Elm S 33° E 90 links
15" White Oak S 18° W 114 links.

1960, MDSH
36.34' North of centerline of M-60.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found nothing, corner falls in fill area for lane to access fields to north.

Set corner 36.34' North of centerline of M-60 per MDSH witnesses in line with fence to North.

SURVEY &
REMONUMENTATION

OCT 24 1994

COMMISSION

LIBER 1760 PAGE 643

C. *Description of monument for corner and accessories established to perpetuate locating the position of the corner:*

Set Harrison monument.
Centerline M-60 South 36.34'
Nail & Spotter 14" Elm N 5° W 26.3'
Nail & Spotter 12" Elm N 5° W 47.2'
Nail & Spotter 12" Hickory N 30° W 61.70'

STATE OF MICHIGAN
DONALD J. DAVIS
PROFESSIONAL SURVEYOR
No. 17617
LICENSED PROFESSIONAL SURVEYOR

Signed by Donald J. Davis Date July 25, 1994

Surveyor's Michigan License No. 17617

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975