

MAR 30 1999

SECRET

APPROVED

Date 12-9-98 ALC
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

For corners in

<u>Calhoun</u> (County)	Located In:	Corner Code #
Clarendon		
1. Public Land Survey	T <u>4S</u> R <u>5W</u>	<u>G-1</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

15 DEC 1998 3:36:54 PM

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER **2087** PAGE **932**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael A. Groat, in a field survey on July 7, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL SURVEY, ROBERT CLARK, DEPUTY SURVEYOR, 1826, INTERSECTED THE NORTH BOUNDARY 38 LINKS EAST OF ECKFORD CORNER; SET POST, B ASH, 14", S 14 DEGREES W, 21 LINKS; B. ASH, 8", S 77 DEGREES W, 21 LINKS.

MICHAEL GROAT, P.S., NOVEMBER, 1997, FOUND STEEL BAR, 36" OAK, 140 DEGREES NAZ, 34.35'; 20" OAK, 23 DEGREES NAZ, 26.36'; TWIN OAKS, 348 DEGREES NAZ, 62.92'; HICKORY, 12", 190 DEGREES NAZ, 30.38'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND FLAT BAR 6" BELOW PAVEMENT. EXCAVATED AND FOUND TILE AND IRON PIPE 1' BELOW SURFACE. THIS CORNER IS 0.30' NORTH OF THE TOWN LINE. ACCEPTED THE POSITION OF THE FLAT BAR AS THE BEST EVIDENCE OF THE ORIGINAL CORNER. SET A BERNTSEN MONUMENT AND MONUMENT BOX.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

THE CORNER IS A BERNTSEN MONUMENT WITH CORNER INFORMATION AND P.S. #39079 STAMPED IN BRASS CAP.

NAIL & TAG IN EASTERLY SIDE OF TWIN OAK, 350 DEGREES NAZ, 62.80'
NAIL & TAG IN EASTERLY SIDE OF 20" OAK, 20 DEGREES NAZ, 26.48'
NAIL & TAG IN WESTERLY SIDE OF 15" HICKORY, 190 DEGREES NAZ, 30.43'
NAIL & TAG IN WESTERLY SIDE OF 36" OAK, 140 DEGREES NAZ, 34.4'
CORNER IS 0.30' NORTH OF TOWN LINE.

NAZ=MAGNETIC AZIMUTH MEASURED FROM NORTH.



Signed by [Signature]

Date 7-9-98

Surveyor's Michigan License No. 39079