

APPROVED

Date 7-27-94  
CALHOUN COUNTY  
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

For corners in  
Calhoun  
(County)

Located In: Corner Code #

28 JUL 94 11:14 A.M.

MIKE B. NORLANDER  
CLERK - REGISTER OF DEEDS

- |                                    |                           |       |
|------------------------------------|---------------------------|-------|
| 1. Public Land Survey              | T <u>4</u> S R <u>5</u> W | G-5   |
|                                    | T _____ R _____           | _____ |
|                                    | T _____ R _____           | _____ |
|                                    | T _____ R _____           | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____ |
|                                    | S _____ T _____ R _____   | _____ |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____ |
|                                    | S _____ T _____ R _____   | _____ |
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

I, Donald J. Davis, in a field survey on July 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1826, Rob Clark MDSH  
Set Post 480.66' South of centerline M-60 in tree row.  
12" Hickory N 9½° E 29½ links.  
8" Hickory S 8° W 4½ links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Found nothing.  
Set corner 480.66' South of centerline of M-60 in tree row to match MDSH information.

SURVEY &  
REMONUMENTATION

OCT 24 1994

COMMISSION

LIBER 1760 PAGE 641

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set Berntsen monument with carsonite marker beside.  
Nail & Spotter 16" Ash South 2.4'  
Nail & Spotter 16" Ash N 10° W 10.5'  
Nail & Spotter 16" Oak N 10° E 12.8'  
Centerline M-60 North 480.66'



Signed by Donald J. Davis  
Surveyor's Michigan License No. 17617

Date July 25, 1994