

**CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

APPROVED
Date Sept 20 1995
**CALHOUN COUNTY
REMONUMENTATION.**

or corners in

<u>Calhoun</u> (County) <u>Clarendon Twp.</u>	Located In:	Corner Code #
Public Land Survey	T <u>4</u> S R <u>5</u> W	<u>G-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

22 SEP 95 10:05 A.M.

ANNE B. NORLANDER
Register of Deeds, Stamp & File Number
CLERK - REGISTER OF DEEDS

Lot No. _____ Recorded Plat _____
Private Claims _____

Frederick J. Cutcher, in a field survey on September 14, 19 95,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Description of original monument and accessories and/or subsequent restoration:
Corner common to Sections 15, 16, 21 & 22, Town 4 South, Range 5 West.
Original Government Survey, December 21, 1825: Maple 14" N 68° W 19 lks.; Maple 12" S 31° E 22 lks.
LCRC Liber 1147, Page 212, May 11, 1978, F.J. Cutcher: Found 1" iron 8" under gravel road surface 6' West of centerline N/S road; 24" Hickory West 37.85' to face; 24" Hickory S 85° W 106.42' to face; Utility Pole N 20° E 128.43' to face.
D. Davis, 11/1981: Found 1" solid bar: 22" Hickory N 85° W 37.5'; 30" Oak N 20° W 105.0'; in centerline of road East; 5' West of centerline N & S.
Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1"x20" iron bar 6' West of centerline N/S road.
Two of the above references were found.



REMONUMENTATION

FEB 22 1996
COMMISSION

Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Replaced 1" iron bar with county issue Harrison marker and is accepted as a careful and faithful reestablishment of the position of the original corner.
6' West of centerline N/S road, in line with centerline of road to base
Nail & spotter in Power Pole N 20° E 128.48'.
Nail & spotter in 30" Oak N 3° W 105.58'.
Nail & spotter in 30" Hickory N 88° W 104.80'.
Top center telephone stanchion S 21° E 62.43'.

LIBER 1022 PAGE 49

Signed by Frederick J. Cutcher Date September 19, 1995
Surveyor's Michigan License No. 24592