

**CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

APPROVED
Date Sept. 20, 1995
**CALHOUN COUNTY
REMONUMENTATION.**

For corners in

<u>Calhoun</u> County	Located In:	Corner Code #
<u>Clarendon Twp.</u>		
1. Public Land Survey	T <u>4</u> S R <u>5</u> W	<u>G-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

22 SEP 95 10:04 A.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Frederick J.

Cutcher

in a field survey on September 14, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Government Survey, December 1825: Ironwood 10" S 86° W 16-1/2 lks.; Ironwood 7" N 11° W 34 lks.

R. Clark, 1826; East 1/4 post, Section 21, Town 4 South, Range 5 West: Ironwood 10" N 86° W 16-1/2 lks.; Ironwood 7" N 11° W 34 lks.

D. Davis, 11/1981: Found plow point; 8" Hickory S 85° W 19.80'; 24" Hickory S 30° W 122.3'.

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1"x18" iron bar (plow point?) in centerline of N/S road.

One of the above witnesses was found.

CORNER
REMONUMENTATION

FEB 22 1996

COMMISSION



2. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced 1"x18" iron bar with County issue Harrison marker and is accepted as a careful and faithful reestablishment of the position of the original corner.

In centerline of N/S Road

11'± South of centerline drive entrance of field to West.

Nail & spotter 18" Hickory S 80° W 19.87'.

Nail & spotter 10" Hickory S 24° W 67.40'.

Nail & spotter 12" Elm N 50° W 39.99'.

Nail & spotter 18" Cherry N 8° E 136.60'.

LIBER 1822 PAGE 44

Signed by Frederick J. Cutcher
Frederick J. Cutcher

Date September 19, 1995

Surveyor's Michigan License No. 24592