

APPROVED
 Date Sept. 20, 1995
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Calhoun</u> (County)	Located In:	Corner Code #
<u>Clarendon Twp.</u>		
1. Public Land Survey	T <u>4</u> S R <u>5</u> W	<u>G-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
 CALHOUN COUNTY
 RECORDED

22 SEP 95 10:03 A.M.

ANNE B. NORLANDER
 CLERK - REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Frederick J. Cutcher, in a field survey on September 15, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 Corner common to Sections 21, 22, 27 & 28, Town 4 South, Range 5 West.
 Original Government Survey, December 1825: Ironwood 6" S 40-1/2° W 14 lks.; Ironwood 6" N 22° E 5 lks.
 R. Clark, 1826: Maple 14" N 68° W 19 lks.; Maple 12" S 31° E 22 lks.
 D. Davis, 11/81: S.E. Corner Section 21; R.R. spike centerline road; 40" W. Oak S 45° E 53.2'; 12" Hickory N 75° E 113.6'.

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found R.R. spike in centerline intersections of roads.
 One of above references was found.

COMMISSION
 REMONUMENTATION

FEB 22 1996

COMMISSION



2. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Replaced R.R. spike with county issue Bernsten marker in monument box and is accepted as a careful and faithful reestablishment of the position of the original corner.
 In centerline intersection of roads.
 Nail & spotter in 48" Oak S 50° E 52.40'.
 Nail & spotter in Power Pole S 42° E 83.68'.
 Top center telephone stanchion N 65° E 48.25'.
 Nail & spotter in 8" Hickory S 30° W 75.85'.

LIBER 1822 PAGE 40

Signed by Frederick J. Cutcher Date September 19, 1995
 Frederick J. Cutcher
 Surveyor's Michigan License No. 24592