

**CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

**APPROVED**  
Date Sept. 20 1995  
**CALHOUN COUNTY  
REMONUMENTATION.**

For corners in

<u>Calhoun</u> <u>Clarendon Twp.</u>	Located In:	Corner Code #
1. Public Land Survey	T <u>4</u> S R <u>5</u> W	<u>G-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

22 SEP 95 10:04 A.M.

ANNE B. NORLANDER  
CLERK - REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Frederick J. Cutcher, in a field survey on September 15, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Corner common to Sections 27, 28, 33 & 34, Town 4 South, Range 5 West.  
Original Government Survey, December 1825: Elm 14" S 62-1/2° W 56-1/2 lks.; Elm 14" S 64° E 27-1/2 lks.  
A. Watkins, 1965: Found iron; 30" Walnut S 80° W 57.5'; 10" Walnut N 45° E 48.85'; 18" Hickory East 54.4'.  
T.P.J., 6/1976: Found 3/4" solid iron; 12" Walnut S 10° E 7.65'; 12" Walnut N 15° E 52.80'; 14" Hickory N 85° E 49.30';

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4"x3' solid iron bar in intersection of centerlines of road extended.  
Three of the above references were found.

COUNTY  
REMONUMENTATION  
  
FEB 22 1996  
COMMISSION



2. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced 3/4"x3' solid iron bar with county issue Bernsten marker and is accepted as a careful and faithful reestablishment of the position of the original corner.  
Reset the 3/4"x3' solid bar on South side of Bernsten marker.  
In intersection of centerlines of roads extended.  
Nail & spotter in 30" Walnut S 20° E 6.77'.  
Nail & spotter in power pole S 30° W 41.17'.  
Nail & spotter in 24" Walnut N 30° E 53.00'.  
Nail & spotter in 36" Walnut S 78° W 59.93'.

LIBER 1822 PAGE 41

Signed by Frederick J. Cutcher Date September 19, 1995  
Surveyor's Michigan License No. 24592