

APPROVED

Date 7-27-94  
CALHOUN COUNTY  
REMONUMENTATION

CALHOUN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Calhoun  
(County)

Located In: Corner Code #

- 1. Public Land Survey T 4 S R 5 W H-3  
T R  
T R  
T R
- 2. Property Controlling in Section S T R  
S T R
- 3. Miscellaneous Property in Sec. S T R  
S T R
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

28 JUL 94 11:14 A.M.

ANNE B. NORLAND  
CLERK - REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Donald J. Davis, in a field survey on July 7, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

|    |    |    |    |    |    |    |   |   |   |   |   |   |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    | ●  |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

- A. Description of original monument and accessories and/or subsequent restoration:  
Clark, 1826  
10" White Oak S 50½° W 32 links.  
30" White Oak S 48° E 43 links.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Set corner at ½ distance on a line from the NE corner of Section<sup>10</sup> to NW corner of Section 9.  
Excavated and found no evidence of corner.

SURVEY &  
REMONUMENTATION

OCT 24 1994

COMMISSION

LIBER 1760 PAGE 644

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Set Harrison monument.  
Nail & Spotter 20" Maple S 80° W 125.00'  
Nail & Spotter 40" Maple North 35.67'  
Nail & Spotter 30" Maple S 70° E 51.05'  
NW corner garage foundation S 20° W 38.10'



Signed by Donald J. Davis  
Surveyor's Michigan License No. 17617

Date July 25, 1994