

**CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

APPROVED
Date Sept. 20 1995
**CALHOUN COUNTY
REMONUMENTATION.**

For corners in

<u>Calhoun</u> (County)	Located In:	Corner Code #
<u>Clarendon Twp.</u>		
1. Public Land Survey	T <u>4</u> S R <u>5</u> W	<u>H-7</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

22 SEP 95 10:04 A.M.

ANNE B. NORLANDER
Register of Deeds Stamp File Number

1. Lot No. _____, Recorded Plat _____
2. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Frederick J. Cutcher, in a field survey on September 15, 1995,
to hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

1. Description of original monument and accessories and/or subsequent restoration:
Original Government Survey, December 1825: Elm 14" S 44° W 39-1/2 lks.; Elm 16" N 2° E 18 lks.
Lewis, 1883: South 1/4 Post Section 15, Town 4 South, Range 5 West: Stone; Elm 18" S 66° E
105-3/4 lks.
1969: South 1/4 Post Section 15, Town 4 South, Range 5 West: R.R. spike; steel corner
post South 21.85'; 28" Maple North 133.05'; 24: Hickory S 80° W 178.23'. (Cal. Co. Rd. Comm.)
LCRC Liber 1147, Page 212, May 11, 1978, F.J. Cutcher: R.R. spike 4.45' South of
centerline E/W road; R.R. spike at road surface; angle iron post S 5° E 21.88';
fence post N 40° E 42.30'.
2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found R.R. spike at road surface. 5' South of centerline E/W road. Found stone 18" below
road surface on West side of R.R. spike.
One of the above references was found.

CUTCHER
REMONUMENTATION

FEB 22 1996

COMMISSION



3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Replaced R.R. spike with county issue Bernsten marker in a monument box and is accepted
as a careful and faithful reestablishment of the position of the original corner.
5' South of centerline E/W road.
Centerline of drive to South, 25.00'.
Nail & spotter 30" Hickory S 80° W 178.27'.
Nail & spotter power pole N 7° E 157.6'.
Nail & spotter 18" Triple Elm N 83° E 126.50'.
Fence post N 40° E 42.30'

LIBER 1822 PAGE 43

Signed by Frederick J. Cutcher Date September 19, 1995
Surveyor's Michigan License No. 24592