

**CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

APPROVED

Date Nov. 20 1995

**CALHOUN COUNTY
REMONUMENTATION
CALHOUN COUNTY
RECORDED**

4 DEC 95 2:25 P.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

CLARENDON TWP.
Corner Code #

<u>CALHOUN</u> (County)	Located in:	
<u>CLARENDON TWP.</u>		
1. Public Land Survey	T <u>4S</u> R <u>5W</u>	<u>H-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Frederick J.
Cutcher

in a field survey on 11/6, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Government Survey, December, 1825: Set post at average distance; Hickory 10" N. 75° E. 34½ lks; Hickory 10" S. 3° W. 37½ lks.

Lewis, 1883: Stone: Elm 8" N. 1½° E. 104 lks.

Don Davis, 1981: P.K. 663.22 West of 1/4 post & 33' North of fence to South.

Survey by Fred Cutcher, Jan. 25, 1989: Referenced to North 1/4 post of Section 27, Town 4 South, Range 5 West: 5/8" iron.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Traversed between Northwest corner & Northeast corner of Section 27, Town 4 South, Range 5 West, set point on line 1/2 way for 1/4 post. Found 1/2" iron rod at this spot 2" below pavement surface. 3' North of centerline T Drive South; 6'± East of fence to South, about in line with fence to North.

None of the above references were found.

REMONUMENTATION

LIBER 1834 PAGE 254

FEB 22 1996

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced 1/2" iron rod with county issue Bernsten marker in a monument box and is accepted as a careful and faithful reestablishment of the position of the original corner.

3' North of centerline T Drive South; 6'± East of fence to South; about in line with fence to North.

Nail & spotter in W. side brace post S 25° W 38.67'.

Nail & spotter in W. side 30" Oak S 40° E 36.32'.

Nail & spotter in E. side R.R. tie post N 15° E 40.83'.

Nail & spotter in N.E. side 24" Maple N 53° W 46.70'.



Signed by Frederick J. Cutcher
Frederick J. Cutcher 24592
Surveyor's Michigan License No. _____

Date November 20, 1995