

APPROVED

Date 7-27-94 WJD
**CALHOUN COUNTY
REMONUMENTATION.**

CALHOUN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

For corners in

Calhoun

(County)

Located In:

Corner Code #

- | | | | | | | | |
|------------------------------------|---|---|---|---|---|---|-----|
| 1. Public Land Survey | T | 4 | S | R | 5 | W | I-4 |
| | T | | | R | | | |
| | T | | | R | | | |
| | T | | | R | | | |
| 2. Property Controlling in Section | S | | T | | R | | |
| | S | | T | | R | | |
| 3. Miscellaneous Property in Sec. | S | | T | | R | | |
| | S | | T | | R | | |

28 JUL 94 11:14 A.M.

ANNE E. NORLANDER
CLERK - REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Donald J. Davis, in a field survey on July 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- Clark, 1826
- 40" White Oak South 66 links.
- 48" White Oak S 43° W 117½ links.

**SURVEY &
REMONUMENTATION**

OCT 24 1994

COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Found no physical evidence of original corner.
- Set corner on occupation line North & South on line between SE corner of Section 10 and NE corner of Section 10.

LIBER 1760 PAGE 645

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set Berntsen monument and monument box.
- RR iron post West 32.70'
- Nail & Spotter 36" Maple N 55° E 26.40'
- Nail & Spotter 30" Cherry S 30° E 48.50'
- Nail & Spotter 18" Ash N 50° W 41.40'



Signed by Donald J. Davis
Surveyor's Michigan License No. 17617

Date July 25, 1994