

**APPROVED**  
 Date Sept 20 1995  
**CALHOUN COUNTY**  
**REMONUMENTATION.**

**CALHOUN COUNTY REMONUMENTATION**  
**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Calhoun</u> (County)	Located In:	Corner Code #
<u>Clarendon Twp.</u>		
1. Public Land Survey	<u>T 4 S R 5 W</u>	<u>I-7</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN  
 CALHOUN COUNTY  
 RECORDED

22 SEP 95 10:05 A.M.

Register of Deeds Stamp & File Number  
 ANNE B. NORLANDER  
 CLERK - REGISTER OF DEEDS

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Frederick J. Cutcher, in a field survey on September 18, 1995, to hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

1. Description of original monument and accessories and/or subsequent restoration:  
 Corner common to Sections 14, 15, 22 & 23, Town 4 South, Range 5 West.  
 Original Government Survey, December 1825: Maple 14" N 39° W 33 lks.; W. Ash 10" East 12 lks.  
 Lewis, 1883: S.E. corner, Section 15, Town 4 South, Range 5 West: Stone; Bro. Oak 18" S 66° E 105-3/4 lks.  
 LCRC Liber 1142, Page 657, March 2, 1978, Ronnie M. Lester; S.E. corner Section 15, Town 4 South, Range 5 West: Set 1/2" bar & cap WNW 101.41' nail & tag S. side 20" Hickory; NW 93.21' nail & tag E. side 20" Oak; NE 97.14' nail & tag W. side 10" Oak.

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found 1/2"x18" iron rod in monument box set by Calhoun County Road Commission in the 1980's. In intersection of N/S & E/W roads, 3' East of centerline N/S road.  
 Two of above references were found.

**CORNER**  
**REMONUMENTATION**

**FEB 22 1996**

**COMMISSION**



2. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Replaced 1/2"x18" iron rod with county issue Bernsten marker in new monument box and is accepted as a careful and faithful reestablishment of the position of the original corner.  
 In line with centerline E/W roads, 3' East of centerline N/S road.  
 Nail & spotter in Power Pole N 52° W 72.55'.  
 Nail & spotter in power pole N 65° E 78.07'.  
 Nail & spotter in 24" Hickory N 73° W 101.0'.  
 Nail & spotter in 24" Oak N 20° W 93.60'

**LIBER 1822 PAGE 47**

signed by Frederick J. Cutcher Date September 19, 1995  
 Surveyor's Michigan License No. 24592