

**CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

APPROVED
Date Sept. 20 1995
**CALHOUN COUNTY
REMONUMENTATION.**

or corners in

<u>Calhoun</u> (County)	Located In:	Corner Code ##
Clarendon Twp.		
Public Land Survey	T <u>4</u> S R <u>5</u> W	<u>I-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

22 SEP 95 10:04 A.M.

ANNE B. NORLANDER
Register of Deeds Stamp & File Number
CLERK - REGISTER OF DEEDS

Lot No. _____, Recorded Plat _____
Private Claims _____

Frederick J. Cutcher, in a field survey on September 18, 19 95,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:
Corner common to Sections 26, 27, 34 & 35, Town 4 South, Range 5 West.
Original Government Survey, December 1825: W. Oak 14" N 46° E 27 lks.; W. Oak 14" S 63-1/2° E 50 lks.
T.P.J., June 1978: centerline road; fence East; Twin 10" Elder N 50° W 48.55'; Twin 14" Basswood S 30° W 101.15'.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1/2"x18" iron rod in monument box set by Calhoun County Road Commission in the 1980's 1' East of centerline N/S road. Fence line to East.
One of above references was found.

REMONUMENTATION
FEB 22 1996
COMMISSION



Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Replaced 1/2"x18" iron rod with county issue Bernsten marker in monument box and is accepted as a careful and faithful reestablishment of the position of the original corner.
1' East of centerline N/S road.
Fence line to East.
Cherry 20" S 30° W 53.94'
Basswood 18" S 23° W 65.70'.
Basswood 8" N 75° E 27.52'.
Basswood 8" S 72° E 28.38'.

LIBER 1822 PAGE 45

Signed by Frederick J. Cutcher Date September 19, 1995
Surveyor's Michigan License No. 24592