

1993

CALHOUN COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

CLERK-REGISTER  
CALHOUN COUNTY, MICH.  
ANNE B. NORLANDER

SEP 1 10 32 AM '93

RECORDED

For corners in Calhoun (County) Located In: Corner Code -#  
 1. Public Land Survey T 4 S. R 5W. K-2  
 T \_\_\_ R \_\_\_  
 T \_\_\_ R \_\_\_  
 T \_\_\_ R \_\_\_  
 2. Property Controlling S \_\_\_ T \_\_\_ R \_\_\_  
 in Section S \_\_\_ T \_\_\_ R \_\_\_  
 3. Miscellaneous S \_\_\_ T \_\_\_ R \_\_\_  
 Property in Sec. S \_\_\_ T \_\_\_ R \_\_\_  
 4. Lot No. \_\_\_ , Recorded Plat \_\_\_  
 5. Private Claims \_\_\_

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2	1			
3													
4	7		8		9		10		11	12			
5													
6	18		17		16		15		14	13			
7													
8	19		20		21		22		23	24			
9													
10	30		29		28		27		26	25			
11													
12	31		32		33		34		35	36			
13													

Frederick J. Cutcher, in a field survey on August 4, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner common to Sections 1 & 2, Town 4 South, Range 5 West, Clarendon Twp.  
 GLO: R. Clark 1826: W. Oak 12" S. 43° W. 48½ links; Hickory 9" N. 44° E. 91½ links

A stone with hole was found and a railroad spike set over hole in stone and was recorded by Donald Gilchrist P.L.S. #13583, Land Corner Records for Calhoun County in Liber 1123, Page 255, July 20, 1977.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found railroad spike over stone per Land Corner Records Liber 1123, Page 255, and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced railroad spike over stone with aluminum marker with brass cap in monument box. 1.6' East of centerline 23 Mile Road; 3'± South of fence to West; 9' South of centerline of M Drive South; P.K. nail in power pole N. 45° W. 71.15'; S.W. cor. porch (siding) N. 38° E. 132.60'; center of 8" Pine S. 80° W. 83.2'; old nail & spotter in 24" Maple N. 56° E. 56.68'.

LIBER 1700 PAGE 144

Signed by Frederick J. Cutcher  
 Surveyor's Michigan License No. 24592



August 23, 1993