

1993

CALHOUN COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

CLERK-REGISTER  
CALHOUN COUNTY, MICH.  
ANNIE R. NORLANDER

SEP 1 10 32 AM '93

RECORDED

For corners in

Calhoun

(County)

Located In:

Corner Code #:

- 1. Public Land Survey T 4S. R 5W. K-3
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

Frederick J. Cutcher

in a field survey on August 23, 1993

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner common to Sections 1, 2, 11 & 12, Town 4 South, Range 5 West, Clarendon Twp.

GLO = W. Oak 14" S. 69 1/2° W. 157 links; W. Oak 7" S. 60 1/2° E. 138 links.

No other record of this corner was found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In November of 1992 I found a 3/4" diameter iron pipe 4" below road surface and used this on a survey. Iron pipe found checks existing lines of occupation.

3/4" diameter iron pipe is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced 3/4" diameter pipe with aluminum marker with brass cap in monument box.

P.K. nail in power pole N. 20° W. 64.20'

N.E. corner of house foundation S. 40° W. 113.60'

P.K. nail in power pole S. 14° E. 90.00'

P.K. nail in pole with telephone stanchion N. 75° W. 84.90'

Signed by Frederick J. Cutcher

Surveyor's Michigan License No. 24592



August 23, 1993

LIBER 1700 PAGE 147