

APPROVED

Date 11/17/99 RM  
CALHOUN COUNTY  
REMONUMENTATION  
For corners in

CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

17 DEC 1999 2:45:52 PM

ANNE R. NORLANDER  
CLERK - REGISTER OF DEEDS

LIBER 2186 PAGE 5

Register of Deeds Stamp & File Number

CALHOUN  
(County)  
CLARENDON TWP.

Located In: Corner Code #

- 1. Public Land Survey T4S R5 W K-9  
T R  
T R  
T R
- 2. Property Controlling S T R  
in Section S T R
- 3. Miscellaneous S T R  
Property in Sec. S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Frederick J. Cutcher, in a field survey on August 17, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO, Robert Clark, Jr., 1825: Elm 14" N. 10° W. 38 lks.; Elm 8" S. 75° E. 3 lks.

Witness Card (no date) A.A.: Ash stake 2 1/2' green angular stone 16"; 20" Elm 41"; S.W. cor. culvert 27.5'.

Witness Card, 8/10/82, Cutcher: Found 3/4" solid iron 4" below pavement. Set P.K. over iron in centerline T Drive South; tel. stan N. 35° E. 32.82'; tel. stan. S 40° E 38.10'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found P.K. over 3/4" iron rod 4" down.

Two of Cutcher's witnesses remain.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced iron pipe with Berntsen Monument in monument box and is accepted as the best available evidence of the position of the original corner.

In centerline T Drive S.; 3 1/2' W. of centerline off 23 Mile Road; Top cen. tel. stan. N. 60° E. 34.4'; top cen. tel. stan. S. 40° E. 38.4'; N. leg of Rowbotham's sign S. 56° W. 40.53'; top cen. tel. stan. N. 38° E. 33.3'.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

Signed by Frederick J. Cutcher  
Surveyor's Michigan License No. 24592

Date 8/18/99



SURVEY &  
REMONUMENTATION

MAR 13 2000

SECTION

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 197  
REVISED MAY 14, 197  
REVISED JAN., 198  
REVISED OCT., 199