

1993

CALHOUN COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

CLERK-REGISTER  
CALHOUN COUNTY, MICH.  
ANNE B. VORLANDER

SEP 1 10 32 AM 93

RECORDED

For corners in  
Calhoun  
(County)

Located In: Corner Code #/

1. Public Land Survey T 4S R 5W M-2

2. Property Controlling in Section S T R

3. Miscellaneous Property in Sec. S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		0
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**Frederick J. Cutcher**, in a field survey on August 4, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

East 1/4 post of Section 1, Town 4 South, Range 5 West, Clarendon Twp. Records of Calhoun County Road Commission (no date or surveyor given): Angle iron; 16" Maple S.W. 53.45'; conc. post S.E. 83.0'; conc. cor. post S. 03° E. 34.5'.

"L" iron in concrete in tile was found by Donald Gilchrist, P.S. #13583 and was recorded July 20, 1977 in Liber 1123, Page 255, of Land Corner Records, Calhoun County Register's Office.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found "L" iron in concrete in tile per LCR Liber 1123, Page 255, and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced "L" iron in concrete in tile with 30" long cast iron Harrison Marker. (Top of Harrison Marker is 6" below gravel road surface). 6' North of centerline of road; 2.5' West of fence to South; P.K. nail in top center of 8" x 8" concrete post S. 30° W. 39.60'; top center of 8" x 8" concrete post S. 03° E. 35.00'; top center of 4" x 4" concrete post S. 50° W. 52.80'; nail in utility pole N. 27° W. 30.00'; nail & spotter in 36" Maple S. 60° W. 53.41'.

LIBER 1700 PAGE 145

Signed by Frederick J. Cutcher  
Surveyor's Michigan License No. 24592



Date August 23, 1993