

**CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

**APPROVED**  
Date Oct 18 1995  
**CALHOUN COUNTY  
REMONUMENTATION.**

For corners in Calhoun (County) Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey	T	<u>4S.</u>	R	<u>6W</u>	<u>A-11</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Section	S	_____	T	_____	R
	S	_____	T	_____	R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED  
26 OCT 95 10:01 A.M.  
Register of Deeds Stamp & File Number  
39079

Trekonsha REGISTER OF DEEDS

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Michael A. Groat, in a field survey on May 10, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

Clark 1826	Gifford 1891
7 Links South of Burlington Cor.	17" Hickory, N 35 3/4 W, 97 Links
18" Elm, N 7 E, 41 Links	4" Maple, S 11 1/2 E, 159 Links
10" Beech, S 3 E, 16 Links	

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found a eye bolt, concrete monument with tile beneth. Found Burlington corner 7 links North. Accepted as a good perpetuation of the original corner.

COMMISSION  
REMONUMENTATION  
  
FEB 22 1996  
  
COMMISSION

LIBER 1828 PAGE 32

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set a Harrison monument in the centerline of roads, from which:

Nail and spotter in 24" Hickory, S 69° E, 67.5'  
Nail and spotter in 30" Oak, N 45° W, 58.9'  
Nail and spotter in 18" Hickory, S 15° E, 114.5'  
Nail and spotter in Utility pole, N 10° E, 301.6'



Signed by Michael A. Groat  
Surveyor's Michigan License No. 39079

Date October 8, 1995