

APPROVED

Date 12-16-97 RRC
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

19 DEC 97 2:37 P.M.

ANNE D. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER 1985 PAGE 523

Register of Deeds Stamp & File Number

For corners in

<u>CALHOUN</u> (County)	Located In:	Corner Code #
TEKONSHA		
1. Public Land Survey	T <u>4S</u> R <u>6W</u>	<u>G-7</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MICHAEL A. GROAT, in a field survey on DECEMBER 5, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL SURVEY BY R. CLARK, DEPUTY SURVEYOR, 1826, SET POST, W. OAK, 18", S71°E, 53 LKS., W. OAK, 10", N38°W, 32 LKS

J.M. GIFFORD, 1889, FOUND LARGE STONE, SET STAKE, APPLE, 6", S11-1/2°W, 90 LKS., APPLE, 8", N14-3/4°E, 116 LKS.

V.D. CAMP, 1919, TILE, NE CORNER OF HOUSE FOUNDATION, SW, 97'; 6" MAPLE, S80°E, 80'; 8" APPLE, N50°E, 67'.

1963, R.L. ROON, 3/8" IRON, S25°W, 47.3'; 14" MAPLE; N65°E, 67.19' T.P.; S70°E, 80.31' 26" MAPLE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

HAD NO MAGNETIC DRAW IN THE AREA. FOUND TWO MAPLE TREES REFERRED TO BY ROON. EACH HAD A NUB OF GROWTH ON THE SIDE. THE HOUSE REFERRED TO BY CAMP APPEARS TO HAVE BEEN ADDED ON TO. THE DIFFERENCE IN THE NEW AND OLD FOUNDATION WAS NOTICEABLE. MEASURING THE DISTANCES GIVEN IN PART "A" FROM THESE OBJECTS CAME WITHIN A 0.3' RADIUS. EXCAVATED AND FOUND THE 3/8" IRON LYING ON ITS SIDE AT A DEPTH OF 2'. UNDER ONE END OF THAT WAS THE TILE. ACCEPTED THE TILE AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER. PLACED A HARRISON MONUMENT IN PLACE OF THE TILE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

HARRISON MONUMENT

ANGLE IRON FENCE POST, SOUTH, 23.79'
NAIL AND TAG IN A 26" MAPLE, S25°W, 47.30'
NAIL AND TAG 30" MAPLE, S70°E, 80.31'
PHONE BOX, N85°E, 163.51'
24" MAPLE, S25°W, 47.3'
30" MAPLE, S70°E, 80.30'

Signed by [Signature]

Date December 10, 1997

Surveyor's Michigan License No. 39079



SURVEY &
REMONUMENTATION

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 22, 1971

APR 07 1998

REVISED JAN., 1993
REVISED OCT., 1998

SECTION