

APPROVED

Date 3-19-97
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTAION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

31 MAR 97 11:38 A.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER 1922 PAGE 726

Register of Deeds Stamp & File Number

For corners in

<u>CALHOUN</u> (County)	Located In:	Corner Code #
Tekonsha Township		
1. Public Land Survey	T <u>4S</u> R <u>6W</u>	<u>G-8</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael A. Groat, in a field survey on February 26, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21	⊕	22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- R. Clark, Deputy Surveyor, 1826, set post 40 chains North of I-9 B Ash, 10", S40°E, 134 Lks, B Ash, 10", S33°W, 72 Lks.
- Gifford, 1891, found one stump of one government bearing tree and stake standing. Set post. Maple, 12" N12°E, 8.22 Lks, Maple, 12", S3°E, 42 Lks.
- M.S.H.D., May, 1964, 1" iron. N33°W, 7.65 feet, 8" Maple; N12°E, 8.22 feet, 6" Maple; East, 2.60 fee, 13 twin Maple

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found witnesses from M.S.H.D and used them to locate the 1" Iron. Dug iron and found that it was a axle shaft. Corner falls in roots of trees. At a depth of 1' the hole fills with water. Found nothing else. Accepted the axle shaft as the best location of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument with standard Calhoun County brass cap stamped with P.S. #39079 and corner information.

- Nail and tag in 18" Twin Maple, East, 2.12 feet (M.S.H.D.)
- Nail and tag in 10" Maple, N33°W, 7.96 feet (M.S.H.D.)
- Nail and tag in 18" Maple, N12°E, 8.62 feet (M.S.H.D)
- Nail and tag in 20" Maple, West, 21.50 feet
- 3' North of fence running East and West
- Carsonite sign on North side



Signed by Michael A. Groat Date March 19, 1997

Surveyor's Michigan License No. 39079

SURVEY &
REMONUMENTATION

APR 07 1998

SECTION